

TECHNICAL SPECIFICATIONS

TERMS OF REFERENCE

For The Rehabilitation of Greenbelt Perimeter Fence, Port of Cagayan de Oro

A. DESCRIPTION

The project aims to Rehabilitate the Greenbelt Perimeter Fence at the Port of Cagayan de Oro to enhance security, ensure safety, and maintain its overall functionality and condition.

B. SCOPE OF WORKS

The supplier/contractor shall undertake the project in accordance with accepted industry standards and procedures.

The services to be rendered by the supplier shall include but not limited to the following:

- 1. **Consultation:** Consult with the Authority, through the Engineering Services Division Technical Staff, to ascertain the objectives and requirements of the services and confirm such requirements with the Authority.
- 2. **Site Inspection:** Conduct ocular inspection and actual measurement at the site.
- 3. **Supply of Materials, Labor, and Equipment** for the following scope of works:

DESCRIPTION OF WORK	UNIT	QUANTITY
1. Removal of damaged fence and excavation works	Lot	1
Supply of Labor for the removal of dilapidated cyclone wire fence and excavation works for the concrete pedestal.		
2. Concreting works	Lot	1
Supply of materials and labor for concreting of post pedestal		
3. Steel fabrication and welding works.	Lot	1
Supply of materials, labor, and equipment for steel fabrication, install cyclone wire, and welding works.		
4. Steel Fence Painting Works	Lot	1
Supply of labor and materials, for repainting works of steel fence		

C. MATERIALS INVOLVED IN THE PROJECT

Portland Cement (40 kls)  
Wash Sand  
3/4 Crushed Gravel  
1/2" thk. Marine Plywood 4'x8'  
2"x2"x8' Coco Lumber  
No. 4" C.W. Nails  
No. 3" C.W. Nails  
Ga. 16 G.I. Tie Wire  
No. 6mm x 50mm x 50mm x 6 ft. x 15 m. Cyclone Wire  
No. 6mm x 50mm x 50mm x 4 ft. x 15 m. Cyclone Wire  
8mm dia. Plain Bar x 6m.  
6mm x 25 x 25mm Angle Bar x 6m.  
1/8 dia. Welding Rod - 6012 (5 kls.)

Cutting Disc Ø100mm ( 25 pcs.)  
6mm x 38mm Flat Bar x 6m.  
50mm dia. G.I. Pipe Sch 40 x 6m.  
10mm dia. Deformed Bar x 6m.  
Rust Converter  
Red Oxide Epoxy Primer  
Epoxy Enamel White  
Baby Roller with Tray-cotton  
Paint Brush 2"  
Epoxy Reducer  
Lacquer Thinner  
8"dia. Waste Pad  
Paint Brush 2"

#### **D. LABOR COMPONENT**

1. Foreman
2. Welder
3. Carpenter
4. Mason
5. Painter
6. Non skilled worker

#### **E. EQUIPMENT**

1. Welding Machine

#### **D. TIMETABLE**

The supplier shall commence the activities effective the day after the receipt of the Notice to Proceed. The mobilization, supply, and delivery of materials, as well as the required works, must be completed within *sixty (60) calendar days* from the commencement of the activities.

#### **E. FIRM AND STAFF REQUIREMENTS**

The supplier shall be responsible for ensuring the timely completion of the project and shall have personnel with adequate technical background, experience, and capability.

The supplier shall provide the minimum appropriate personal protective equipment (PPE) such as hard hats, vests, face masks, and face shields, and shall provide disinfecting solutions such as alcohol and sanitizers to their staff and crew.

#### **F. SCHEDULE OF PAYMENTS**

All payments shall be processed only upon completion and issuance of a Certificate of Completion and Acceptance, subject to accounting and auditing rules and regulations.

#### **G. BUDGET**

The Approved Budget of the Contract for the project for the *Rehabilitation of Greenbelt Perimeter Fence, Port of Cagayan de Oro* is Six Hundred Eighty-Six Thousand Sixty-seven Pesos (**₱ 686,067.00**).

**H. MODE OF PROCUREMENT/QUALIFICATION OF BIDDERS**

The contract for the *Rehabilitation of Greenbelt Perimeter Fence, Port of Cagayan de Oro* shall be procured through Small Value Procurement, in accordance with Section 53.9 and Annex “H” of the 2016 Revised Implementing Rules and Regulations of RA 9184.

Interested bidders must submit their proposals on or before October 29, 2024, at 8:30 AM, at the address provided. Prospective bidders will be evaluated based on a non-discretionary “pass/fail” criterion, and shall submit the updated/renewed printed copies of the following documents as part of the technical/financial proposal/envelope:


**Technical Proposal:**

- PhilGEPS Certificate of Registration, with corresponding Annexes
- Certificate of Registration from SEC/DTI whichever is applicable
- Valid Mayor’s Permit
- PCAB License
- Income/Business Tax Return
- Omnibus Sworn Statement

**Financial Proposal:**

- Duly accomplished, Request for Quotation

Prepared by:

  
**MARC M. AVELLANA**  
Supervising Engineer A

Approved:

  
**ANTONIO M. TORCINO, JR.**  
OIC - ESD-Manager